



# DOCS 200

## Medical Configuration

Superior Reliability - Easy Serviceability  
Modular and Turn-Key System For Easy Installation

## ON-SITE OXYGEN GENERATOR

Characteristic	Value / Description
Discharge flow rate	200 lpm   12 m <sup>3</sup> per hour   425 scfh   840 lbs per day   380 kg per day
O <sub>2</sub> purity @ discharge flow rate	93% +/- 3%
O <sub>2</sub> output pressure	20 – 100 psig   1.4 – 6.9 barg
Operating temperature	0°F to 120°F   -18°C – 49°C
Power requirements	
Site power source	380/460 VAC +/- 10%, 50/60 Hz +/- 3%, 3-Phase, 60/50 Ampere
Plant	380/460 VAC , 50/60 Hz, 3-Phase, 42/36 FLA
Average power consumption	7.7 kW at 20 psig (1.4 barg) output pressure 8.0 kW at 55 psig (3.8 barg) output pressure 8.4 kW at 100 psig (6.9 barg) output pressure
Process outlet connection	1/2" Internal NPT Fitting
Unit footprint dimensions (nom.)	72" L x 85" W x 66" H   183 cm L x 216 cm W x 169 cm H
Crated dimensions (nom.)	82" L x 96" W x 79" H   208 cm L x 244 cm W x 201 cm H
Unit weight (nom.)	3,148 lbs   1428 kg
Crated Weight (nom.)	4,200 lbs   1907 kg
Average scheduled maintenance cost	\$120 - \$150 per month
Average operating cost @ 55 psig	\$0.20 - \$0.27 per 100 scf   \$0.07 - \$0.10 per m <sup>3</sup>
Additional available options	Remote monitoring & diagnostics suite 4-20 mA Communication to external controller (0-10V standard) Mass flow control assembly Automatic sleep mode feature for low-demand situations Platinum 3 plus 10 Warranty

<sup>1</sup> Performance parameters stated at standard conditions (59°F 14.7 psia 0% RH | 15°C 101.325kPa 0% RH). Operation in atypical conditions may affect performance. For more information, please consult with your PCI technical representative.

<sup>2</sup> Available in CE compliant and FDA cleared configurations.

<sup>3</sup> Electrical enclosure cUL listed.